

**17-CDBG-12013 - Seeley County Water District –Water Distribution System Improvement Project**  
**Bid Comparison and**  
**Results**

No	Item	A&R Construction	Pyramid Construction & Aggregates
1	MOBILIZATION PER SECTION 01505 "MOBILIZATION" OF THE TECHNICAL SPECIFICATIONS.	\$ 75,000.00	\$ 66,700.00
2	IMPLEMENTATION OF TRAFFIC CONTROL PLANS INCLUDING GENERAL TRAFFIC CONTROL NOTES PER PLAN SHEETS 16 AND 17, AND TECHNICAL SPECIFICATIONS.	\$ 20,328.00	\$ 30,600.00
3	POTHOLING OF THE EXISTING UNDERGROUND UTILITIES AND PIPELINES PER THE PLANS AND THE SPECIFICATIONS.	\$ 40,230.00	\$ 36,720.00
4	IMPLEMENTATION OF EROSION CONTROL PLAN INCLUDING BMPS PER PLAN SHEET 2.	\$ 21,270.00	\$ 41,820.00
5	PROVIDE CONSTRUCTION STAKING PER SECTION 01722 "SURVEYING" OF THE TECHNICAL SPECIFICATIONS.	\$ 40,880.00	\$ 25,000.00
6	HYDROSTATIC TESTING AND DISINFECTION OF WATER PIPELINES IN STRICT CONFORMANCE WITH TECHNICAL SPECIFICATION SECTIONS 02666 AND 02670.	\$ 7,500.00	\$ 20,400.00
7	SAWCUT EXISTING A.C. PAVEMENT FOR THE FULL DEPTH OF A.C. PAVEMENT.	\$ 9,888.00	\$ 13,447.68
8	REMOVE AND DISPOSE OF EXISTING A.C. PAVEMENT MATERIAL.	\$ 5,040.00	\$ 3,264.24
9	SAWCUT EXISTING P.C.C. DRIVEWAY FOR THE FULL DEPTH OF THE SIDEWALK / DRIVEWAY.	\$ 510.00	\$ 612.00
10	REMOVE AND DISPOSE OF EXISTING P.C.C. SIDEWALK / DRIVEWAY.	\$ 500.50	\$ 399.84
11	EXISTING WATER SERVICE TO BE ABANDONED IN PLACE. REMOVE AND DISPOSE OF THE EXISTING WATER METER, METER ENCLOSURE AND ANY PIPELINE COMPONENTS.	\$ 9,225.00	\$ 7,318.50

**17-CDBG-12013 - Seeley County Water District –Water Distribution System Improvement Project**  
**Bid Comparison and**  
**Results**

12	REMOVE EXISTING WATER VALVES, VALVE RISERS, COUPLING ADAPTERS, DUCTILE IRON CROSSES OR TEES, ELBOWS AND OTHER FITTINGS AND HARDWARE. DISPOSE OF ANY PIPELINE COMPONENTS. PLUG THE EXISTING ABANDONED WATER PIPELINES AT LOCATIONS AS INDICATED ON THE IMPROVEMENT PLANS.	\$ 2,000.00	\$ 73,440.00
13	COMPLETE ALL EXISTING AND NEW WATER PIPELINE CONNECTION TIE-INS IN STRICT CONFORMANCE WITH THE PLANS AND SPECIFICATIONS.	\$ 7,112.00	\$ 30,000.00
14	INSTALL NEW 12-INCH DIAMETER AWWA C-900 DR-18 PVC WATER PIPELINE PER PLANS. INCLUDE TRENCH EXCAVATION ACTIVITIES AND BACKFILL ACTIVITIES.	\$ 108,680.00	\$ 268,064.16
15	INSTALL NEW 8-INCH DIAMETER AWWA C-900 DR-18 PVC WATER PIPELINE PER PLANS. INCLUDE TRENCH EXCAVATION ACTIVITIES AND BACKFILL ACTIVITIES.	\$ 134,617.60	\$ 311,497.36
16	INSTALL NEW 1-INCH DIAMETER WATER SERVICE PIPELINE COPPER PER IMPROVEMENT PLANS. INCLUDE TRENCH EXCAVATION ACTIVITIES AND BACKFILL ACTIVITIES.	\$ 56,550.00	\$ 97,222.50
17	INSTALL ALL PIPES AND FITTINGS PER CONNECTION DETAIL 1 ON PLAN SHEET 11, TO INCLUDE REFERENCED DETAILS AND IN ACCORDANCE WITH PROJECT PLANS AND SPECIFICATIONS.	\$ 15,496.00	\$ 20,024.64
18	INSTALL ALL PIPES AND FITTINGS PER CONNECTION DETAIL 2 ON PLAN SHEET 11, TO INCLUDE REFERENCED DETAILS AND IN ACCORDANCE WITH PROJECT PLANS AND SPECIFICATIONS.	\$ 9,376.00	\$ 12,557.22
19	INSTALL ALL PIPES AND FITTINGS PER CONNECTION DETAIL 3 ON PLAN SHEET 11, TO INCLUDE REFERENCED DETAILS AND IN ACCORDANCE WITH PROJECT PLANS AND SPECIFICATIONS.	\$ 5,160.00	\$ 8,688.36
20	INSTALL ALL PIPES AND FITTINGS PER CONNECTION DETAIL 4 ON PLAN SHEET 11, TO INCLUDE REFERENCED DETAILS AND IN ACCORDANCE WITH PROJECT PLANS AND SPECIFICATIONS.	\$ 16,993.00	\$ 25,966.14

**17-CDBG-12013 - Seeley County Water District –Water Distribution System Improvement Project**  
**Bid Comparison and**  
**Results**

21	INSTALL ALL PIPES AND FITTINGS PER CONNECTION DETAIL 5 ON PLAN SHEET 11, TO INCLUDE REFERENCED DETAILS AND IN ACCORDANCE WITH PROJECT PLANS AND SPECIFICATIONS.	\$ 13,494.00	\$ 14,564.00
22	INSTALL ALL PIPES AND FITTINGS PER CONNECTION DETAIL 6 ON PLAN SHEET 11, TO INCLUDE REFERENCED DETAILS AND IN ACCORDANCE WITH PROJECT PLANS AND SPECIFICATIONS.	\$ 11,238.00	\$ 11,644.00
23	INSTALL ALL PIPES AND FITTINGS PER CONNECTION DETAIL 7 ON PLAN SHEET 11, TO INCLUDE REFERENCED DETAILS AND IN ACCORDANCE WITH PROJECT PLANS AND SPECIFICATIONS.	\$ 16,548.00	\$ 23,285.00
24	INSTALL ALL PIPES AND FITTINGS PER CONNECTION DETAIL 8 ON PLAN SHEET 11, TO INCLUDE REFERENCED DETAILS AND IN ACCORDANCE WITH PROJECT PLANS AND SPECIFICATIONS.	\$ 16,585.00	\$ 19,205.00
25	INSTALL ALL PIPES AND FITTINGS PER CONNECTION DETAIL 9 ON PLAN SHEET 12, TO INCLUDE REFERENCED DETAILS AND IN ACCORDANCE WITH PROJECT PLANS AND SPECIFICATIONS.	\$ 16,867.00	\$ 22,064.00
26	INSTALL ALL PIPES AND FITTINGS PER CONNECTION DETAIL 10 ON PLAN SHEET 12, TO INCLUDE REFERENCED DETAILS AND IN ACCORDANCE WITH PROJECT PLANS AND SPECIFICATIONS.	\$ 13,288.00	\$ 14,905.00
27	INSTALL ALL PIPES AND FITTINGS PER CONNECTION DETAIL 11 ON PLAN SHEET 12, TO INCLUDE REFERENCED DETAILS AND IN ACCORDANCE WITH PROJECT PLANS AND SPECIFICATIONS.	\$ 1,214.00	\$ 6,540.00
28	INSTALL ALL PIPES AND FITTINGS PER CONNECTION DETAIL 12 ON PLAN SHEET 12, TO INCLUDE REFERENCED DETAILS AND IN ACCORDANCE WITH PROJECT PLANS AND SPECIFICATIONS.	\$ 11,207.00	\$ 14,273.00

**17-CDBG-12013 - Seeley County Water District –Water Distribution System Improvement Project**  
**Bid Comparison and**  
**Results**

29	INSTALL 12-INCH DIAMETER 45-DEGREE DUCTILE IRON ELBOW WITH RESTRAINED JOINT FITTINGS HARDWARE AND P.C.C. THRUST BLOCK.	\$ 2,310.00	\$ 9,130.00
30	INSTALL 8-INCH DIAMETER 11.25-DEGREE DUCTILE IRON ELBOW WITH RESTRAINED JOINT FITTINGS HARDWARE AND P.C.C. THRUST BLOCK.	\$ 1,990.00	\$ 8,756.00
31	INSTALL BLOW-OFF ASSEMBLY INCLUDING SERVICE SADDLE, CORPORATION STOP, SERVICE PIPELINE, BLOW-OFF, ENCLOSURE, ANGLE STOPS, BRASS FITTINGS, BRASS COUPLINGS, 316 STAINLESS STEEL HARDWARE AND BRASS CONNECTIONS PER IMPROVEMENT PLANS.	\$ 28,400.00	\$ 293,672.00
32	REMOVE EXISTING FIRE HYDRANT, SPOOL, BURY, PIPELINE, VALVE AND APPURTENANCES. DISPOSE OF THE REMOVED COMPONENTS.	\$ 2,000.00	\$ 36,720.00
33	INSTALL FIRE HYDRANT ASSEMBLY INCLUDING DUCTILE IRON LINE SIZE X LINE SIZE X 6-INCH TEE, RESILIENT WEDGE GATE VALVE, VALVE RISER, FRAME AND COVER, 6-INCH DIAMETER AWWA C-900 DR 18 PVC HORIZONTAL PIPELINE BETWEEN THE VALVE AND BURY, RESTRAINED JOINT FITTINGS, DUCTILE IRON BURY, BREAK-OFF SHEAR SPOOL, FIRE HYDRANT, 316 STAINLESS STEEL HARDWARE AND P.C.C. THRUST BLOCKS PER IMPROVEMENT PLANS. INCLUDE TRENCH EXCAVATION ACTIVITIES AND BACKFILL ACTIVITIES.	\$ 47,460.00	\$ 133,872.00
34	INSTALL 1-INCH WATER SERVICE CONNECTION ASSEMBLY, INCLUDING SERVICE SADDLE, CORPORATION STOP, SERVICE PIPELINE, WATER METER, WATER METER ENCLOSURE, ANGLE STOPS, BRASS FITTINGS, BRASS COUPLINGS, 316 STAINLESS STEEL HARDWARE AND BRASS CONNECTIONS PER IMPROVEMENT PLANS. MAINTAIN THE EXISTING WATER SERVICE ACTIVE UNTIL THE NEW WATER SERVICE IS READY TO BE ACTIVATED PER SPECIAL CONDITIONS. INCLUDE TRENCH EXCAVATION ACTIVITIES AND BACKFILL MATERIALS COST.	\$ 110,250.00	\$ 223,425.00

17-CDBG-12013 - Seeley County Water District –Water Distribution System Improvement Project

Bid Comparison and

Results

35	LOWER THE EXISTING WATER VALVE RISER TO 0.30 FOOT BELOW GRADE PRIOR TO PAVING ACTIVITIES. RAISE THE WATER VALVE RISER AFTER PAVING ACTIVITIES.	\$ 18,765.00	\$ 22,032.00
36	INSTALL CLASS II BASE MATERIAL BENEATH NEW A.C. PAVEMENT AND P.C.C. INFRASTRUCTURE.	\$ 8,930.00	\$ 35,955.00
37	INSTALL NEW A.C. PAVEMENT IN WATER PIPELINE AND WATER SERVICE PIPELINE TRENCHES AND COLD PLANED AREAS.	\$ 77,468.00	\$ 76,398.00
38	RESTRIPING EXISTING STRIPING REMOVED FOR CONSTRUCTION OF PIPELINES.	\$ 2,500.00	\$ 15,300.00
39	OBTAIN IID CUSTOMER SERVICE PROPOSAL FOR SECURING OF POWER POLE IN ALLEYWAY.	\$ 20,000.00	\$ 20,000.00
	<b>Total</b>	<b>\$ 1,006,870.10</b>	<b>\$ 2,095,482.64</b>

\*A&R Construction is deemed, lowest, most responsive and responsible bidder.