

125,000 GALLON TANK REPLACEMENT

ITEM	QUAN	UNIT	ITEM	UNIT COST	AMOUNT
1	1	LS	Mobilization/ Demobilization, Temporary Facilities, Construction Sign, Insurance, Payment Bond, Taxes, Permits, Fees and Similar Expenses	\$ 7,500.00	\$ 7,500.00
2	1	LS	Demolish existing bolted steel tank installed in the year 2000. Remove and dispose of the tank. The existing foundation is to remain.	\$ 5,600.00	\$ 5,600.00
3	1	LS	Provide tank submittal	\$ 5,000.00	\$ 5,000.00
4	1	LS	Install 1/2" fibre expansion joint material on top of the existing tank pad and prior to installation of the tank floor panels to protect the bottom of the panels.	\$ 750.00	\$ 750.00
5	1	LS	Install fusion powder coated bolted steel tank, nominal dimensions 30' diameter and 24' high, including all accessories as shown on the plans. Connect tank to existing piping.	\$ 103,000.00	\$ 103,000.00
6	1	LS	After installation, complete holiday testing of the interior coating. Repair all holidays.	\$ 1,200.00	\$ 1,200.00
7	1	LS	Provide bacteria (Bac-T) and VOC sampling and testing by an approved lab.	\$ 1,500.00	\$ 1,500.00
			Subtotal Construction:		\$ 124,550.00

Total Project Estimate: \$ 124,550.00